

**BURNETT COUNTY HIGHWAY DEPARTMENT • 8150 STH-70, SIREN, WI 54872
REQUEST FOR BIDS • HOT MIX ASPHALT (HMA) PAVING PROJECTS
BURNETT COUNTY, WISCONSIN**

The Burnett County Highway Department will receive sealed bids from qualified contractors for Hot Mix Asphalt (HMA) paving work on various County Trunk Highway projects.

All work shall include labor, materials, equipment, traffic control, and incidentals necessary to complete the projects in accordance with applicable Wisconsin Department of Transportation (WisDOT) Standard Specifications for Highway and Structure Construction and LRIP requirements where applicable.

Burnett County reserves the right to accept or reject any or all bids and to waive any informalities in the bidding process if deemed in the best interest of the County.

PROJECT DESCRIPTIONS

PROJECT 1

CTH D – LRIP Project Request #139120

Location: County Trunk Highway D from Fire Number 8550 to Martin Road

Length: 2.73 Miles

Road Width: 24 Feet

Scope of Work Placement of Hot Mix Asphalt pavement.

Burnett County will haul asphalt mix from the Don Johnson pit and supply the mix to the paving contractor (Monarch Paving Company) for placement. Burnett County will provide traffic control

Bid Items Requested

Contractors shall provide pricing for the following options:

Option 1

- 4LT 58-34S Hot Mix Asphalt
- 4 inches compacted thickness
- 24-foot paving width

Option 2

- 4MT 58-34S Hot Mix Asphalt
- 4 inches compacted thickness
- 24-foot paving width

LRIP Project Number: 139120

PROJECT 2

CTH F – LRIP Project #19285

Location: County Trunk Highway F from Peet Post Office to Highland Road

Length: 1.00 Mile

Road Width: 24 Feet

Scope of Work Placement of Hot Mix Asphalt pavement.

Contractors shall provide **two pricing options:**

Option A – County Hauled Mix

Burnett County Highway Department will haul asphalt mix to the project site and do traffic control

Option B – Contractor Hauled Mix

Contractor will provide hauling of asphalt mix and traffic control

HMA Specifications

- 4LT 58-34S Hot Mix Asphalt
- 4 inches compacted thickness
- 24-foot paving width
- Don Johnson Pit

LRIP Project Number: 19285

PROJECT 3

CTH A – Mill and Overlay Project

Location: County Trunk Highway A from the intersection of CTH A and CTH H to Christener Road

Length: 1.75 Miles

Road Width: 22 Feet

Scope of Work Mill the existing asphalt pavement and place new Hot Mix Asphalt overlay.

Contractors shall provide **two pricing options:**

Option A – County Hauled Mix

Burnett County will haul asphalt mix to the project site and provide traffic control

Option B – Contractor Hauled Mix

Contractor will provide hauling of asphalt mix and provide traffic control

Project Specifications

Milling

- Mill existing asphalt pavement to a depth of 1.5 inches

Overlay

- Place 2 inches of 4LT 58-34S Hot Mix Asphalt
- 24-foot paving width
- Paffel Pit

GENERAL REQUIREMENTS

All work shall comply with:

- Wisconsin DOT Standard Specifications for Highway and Structure Construction
- Applicable LRIP project requirements
- Traffic control standards and MUTCD guidelines

Contractors shall provide all necessary:

- Labor
- Equipment
- Materials
- Incidentals required to complete the project

Contractors must provide proof of:

- Liability insurance
- Worker's compensation coverage
- Applicable licensing

BID SUBMISSION

Sealed bids must be clearly marked:

“HMA Paving Bid – Burnett County Highway Department”

Bids shall be submitted to:
Burnett County Highway Department
7410 County Road K
Siren, WI 54872

Bid Deadline:

April 15 7:50

April 15 8:00 bid opening

Late bids will not be accepted

CONTACT INFORMATION

Questions regarding the projects may be directed to:

Jeremy Burton

Burnett County Highway Department

Phone: 715-523-0570

Email: Jeremy.burton@burnettcountywi.gov