PROPRIETARY RIGHTS CLAUSE - INFORMATION AND DATA CONTAINED ON THIS DRAWING IS CONFIDENTIAL. IF GIVEN TO AN ENTITY NOT HAVING A CONTRACTUAL RELATIONSHIP WITH THE ENGINEER, THIS INFORMATION SHALL NOT BE USED WITHOUT PRIOR WRITTEN PERMISSION. THIS LEGEND SHALL BE MARKED ON ANY REPRODUCTIONS HEREOF IN WHOLE OR IN PART. COMPTON ENGINEERING, INC. © COPYRIGHT 1996

NORTH

SCALE: 1"=1500'

PROPOSED IMPROVEMENTS (SHED 5):
- REHAB L.S. #5

PROPOSED FUTURE IMPROVEMENTS (SHED 5):
- IMPROVE GRAVITY SEWER LINES AND MANHOLES BY REHABILITATION/ REPLACEMENT
- EXISTING GRAVITY SEWER: **±3,000 L.F. 8"Ø G.S.**

PROPOSED FUTURE IMPROVEMENTS (SHED 8):
- IMPROVE GRAVITY SEWER LINES AND MANHOLES BY REHABILITATION/ REPLACEMENT
- EXISTING GRAVITY SEWER: **±4,800 L.F. 8"Ø G.S.**
- REHAB L.S. #8

PROPOSED IMPROVEMENTS (SHED 9):
- REHAB L.S. #9
- **REPLACE ±3,700 L.F. 6"Ø FORCE MAIN** (DIRECTIONAL BORE)

PROPOSED FUTURE IMPROVEMENTS (SHED 9)
- IMPROVE GRAVITY SEWER LINES AND MANHOLES BY REHABILITATION / REPLACEMENT
- EXISTING GRAVITY SEWER: **±7,200 L.F. 8"Ø G.S.**

PROPOSED FUTURE IMPROVEMENTS (SHED 44):
- REHAB L.S. #44

PROPOSED IMPROVEMENTS (SHED 11):
- IMPROVE GRAVITY SEWER LINES AND MANHOLES BY REHABILITATION/ REPLACEMENT
- EXISTING GRAVITY SEWER: **±5,800 L.F. 8"Ø G.S.** **±2,000 L.F. 12"Ø G.S.** **±600 V.F. MANHOLES (±48 EA.)**
- REHAB L.S. #11

PROPOSED FUTURE IMPROVEMENTS (SHED 2):
- REHAB L.S. #2

PROPOSED IMPROVEMENTS (SHED 1):
- IMPROVE GRAVITY SEWER LINES AND MANHOLES BY REHABILITATION/ REPLACEMENT
- EXISTING GRAVITY SEWER: **±300 L.F. 6"Ø G.S.** **±24,000 L.F. 8"Ø G.S.** **±200 L.F. 12"Ø G.S.** **±1,200 V.F. MANHOLES (±101 EA.)**

PROPOSED IMPROVEMENTS (SHED 88):
- IMPROVE GRAVITY SEWER LINES AND MANHOLES BY REHABILITATION/ REPLACEMENT
- EXISTING GRAVITY SEWER: **±3,400 L.F. 8"Ø G.S.** **±100 L.F. 12"Ø G.S.** **±800 L.F. 15"Ø G.S.** **±300 V.F. MANHOLES (±20 EA.)**
- REHAB L.S. #88

PROPOSED FUTURE IMPROVEMENTS (SHED 22):
- REHAB L.S. #22

PROPOSED IMPROVEMENTS (SHED 18):
- **REPLACE ±2,300 L.F. 6"Ø FORCE MAIN** (DIRECTIONAL BORE)

PROPOSED FUTURE IMPROVEMENTS (SHED 20):
- REHAB L.S. #20

PROPOSED FUTURE IMPROVEMENTS (SHED 28):
- REHAB L.S. #28

PROPOSED IMPROVEMENTS (SHED 18):
- **INSTALL ±1,200 L.F. 8"Ø FORCE MAIN** (DIRECTIONAL BORE)

PROPOSED IMPROVEMENTS (SHED 79,87,88):
- **INSTALL ±3,800 L.F. 12"Ø FORCE MAIN** (DIRECTIONAL BORE)

CITY LIMITS

TO I-10

MISSISSIPPI STATE HIGHWAY 609

U. S. HIGHWAY 90

Legend
- SEWER LINE
- PRIVATE SEWER LINE
- SEWER FORCE MAIN
- JCUA FORCE MAIN
- CITY LIMITS
- PROPOSED FORCE MAIN IMPROVEMENTS
- MANHOLE
- JCUA LIFT STATION
- CITY OF OCEAN SPRINGS LIFT STATION
- PRIVATE LIFT STATION
- PROPOSED SYSTEM UPGRADES

Rev. No. A

	DATE	DESCRIPTION	BY	APVD
A	06/13/17	ISSUED FOR DRAFT FACILITIES PLAN	NMB	WAD

COMPTON ENGINEERING, INC.
Engineering, Surveying, and Environmental Services
1706 Convent Avenue
Pascagoula, Mississippi 39567
Phone: (228) 762-3970 Fax: (228) 769-9079
E-mail: compton@comptonengineering.com

CITY OF OCEAN SPRINGS
SEWER SYSTEM MAP

WASTEWATER FACILITY PLAN
EXISTING SYSTEM WITH IMPROVEMENTS

SCALE: 1" = 1500'
JOB NO.: 216-039.005
DATE:
DSGN.: WAD
DWG. BY: NMB
CHK.: WAD
APVD.:

VERIFY SCALES
BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET ADJUST SCALES ACCORDINGLY

0 1"

FIGURE 1